


**TOLERANCES:**  
Construction tolerances between frames is -0mm +2mm. Frames are manufactured and assembled to +0mm -2mm.

A4


**NOTES**  
THIS DRAWING IS COPYRIGHT. DO NOT SCALE THIS DRAWING. CONTRACTORS MUST CHECK ALL DIMENSIONS ON SITE, ONLY FIGURED DIMENSIONS TO BE WORKED FROM. ALL ERRORS AND DISCREPANCIES MUST BE IMMEDIATELY REPORTED TO THE DESIGN OFFICE OF EOS FRAMING LTD

Studs have swaged ends to fit inside the track so that both studs & tracks are the same width to assist in providing as flush a finish as is possible

TRIPLE JAMBS CONSIST OF SINGLE STUD FIXED TO PRE-ASSEMBLED DOUBLE STUD.  
  
QUAD JAMBS CONSIST OF 2 NO. PRE-ASSEMBLED DOUBLE STUDS FIXED TOGETHER WITH PLATES AS SPECIFIED BY EOS ENGINEERS.




**TRIPLE JAMB**



**QUAD JAMB**

**NOTE:-**  
DOUBLE STUDS ARE MANUFACTURED AT 175mm WIDE AS STANDARD.  
  
DOUBLE STUDS CAN BE MANUFACTURED BETWEEN 100mm AND 225mm WIDE FOR NON-STANDARD APPLICATIONS. PLEASE ENQUIRE WITH EOS.

FOR HEAD FIXINGS PLEASE REFER TO STANDARD DETAILS 273 (DHT DEFLECTION HEAD TRACK) OR 265 (DHB DEFLECTION HEAD BRACKETS)

Title: TYPICAL TRIPLE & QUAD JAMB DETAILS (S & T)					STAGE:		
					Preliminary:	<input type="checkbox"/>	
					Approval:	<input type="checkbox"/>	
					Construction:	<input checked="" type="checkbox"/>	
Drawn By: TE	Scale: NTS	Drawing No. 279	Revision: -	Approved By: AH/KB	Date: AUG 2020		

EOS Framing Ltd, Helington Lane, Aycliffe Industrial Park, Newton Aycliffe, County Durham, DL5 6QG, Tel: 01325 303030